

OSB and FOSB

The future of engineered wood products



JUNE 2025

What is OSB and FOSB?





Oriented strand board (OSB)

OSB is a reconstituted wood panel formed by layering wood strands together at specific orientations to achieve structural properties of plywood at a reduced manufacturing cost


Fine OSB (FOSB)


FOSB is a wood panel with an OSB core and 'fine' surface layers; this provides a board with a surface finish similar to MDF but enhanced structural integrity




Why OSB?

OSB is a ubiquitous building product in North America and Europe, on par with structural plywood. In Asia, OSB consumption is rapidly growing (10yr CAGR: 28%) and displacing structural plywood as observed in other geographies







Sources: FAO Data

(2) Note: Plywood includes LVL



⁽¹⁾ Apparent consumption = Production + Imports – Exports

Why FOSB?

FOSB is intrinsically superior to PB and MDF in most properties

Material		Particleboard	FOSB	MDF
Fabricator Joiner	Processing Machine impact	Prone to edge breakout	FOSB & MDF Similar	FOSB & MDF Similar
	Weight / Handling	600-650 kg/m2	620-680 Kg/m2	720-740 Kg/m2
	Screw holding	Less likely to split on edge	Less likely to split on edge	
	Face and edge finishing	Superior edge tape adherence	Superior edge tape adherence	
Home Owner	Strength / Rigidity		Sag 50% of MDF	
	Moisture resilience Durability		Superior vs MR MDF and particleboard MR	
	Laminating		Smoothness & colour are key	Smoothest
	Indoor air quality	UF/MUF resin	PMDI resin (No added formaldehyde)	UF/MUF resin

FOSB advantages over PB

- → Strength, stiffness and moisture resistance
- No added formaldehyde resin
- → Ability to control board properties, density etc, for specific uses

FOSB advantages over MDF

- → As above, plus lighter weight
- → Less likely to split when screwing into edges


MDF advantages over FOSB are limited

- Premium market finishes including face machining for vinyl wrap or lacquer finish
- → Market inertia given the established market position of MDF



Supportive macro construction trends

Key construction sector trends are driving increased demand and intensity of construction wood panels



Insights:

- Increasing demand of multi-unit residential construction leading to increased flooring requirements and optionality
- Rising demand for lightweight construction materials over traditional concrete and steel e.g. wood panel based commercial mid-floor systems
- Increasing uptake of new residential construction systems e.g. Rigid Air Barriers (RAB)
- Sustainable building materials with environmental credentials



Plant overview – Laminex Taupō

Leading investment in the New Zealand wood panels manufacturing industry



- New plant will utilise advanced technology to produce a wide range of quality, cost competitive and superior products with diverse applications in furniture, joinery and the broader construction sector
- → Provides a platform to explore innovative engineered wood product (EWP) opportunities across wall systems, roof sheathing and mass timber
- The new wood panel production line will supersede the current particleboard line which will be decommissioned
- → At production of 120,000m3, the investment is expected to generate mid-cycle incremental EBIT of approximately \$40m by FY31

Capacity

160,000m3 p.a. Capacity will enable

supply to domestic & export markets

Health & Safety

Best practice safety standards through automation and earthquake resilience

Sustainability

On-site biomass energy generation derived from production waste

Competitive Products

Creates a leading wood panels position in NZ

Local economy

150+ people onsite during delivery, positively contributing to the local economy

Innovation & Productivity


Investment in advanced technologies improving NZ productivity

Incremental returns @ mid cycle

EBIT of c.\$40m by FY31



Manufacturing process



Product innovation pipeline


The new plant will enable the development of a wide range of engineered wood products











up to 7m long

Delivery programme

Plant nearing completion, 1st board targeted in early FY27

